



SECTION 11160

LOADING DOCK EQUIPMENT

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Loading dock equipment of the following types:
 - 1. Dock levelers.
 - 2. Vehicle restraints.
 - 3. Dock seals.
 - 4. Dock shelters.
 - 5. Dock lifts.

1.2 RELATED SECTIONS

- A. Section 03300 - Cast-In-Place Concrete: Coordination with dock construction.
- B. Section 16050 - Basic Electrical Methods and Materials: Coordination with power requirements and controls/safety circuits.

1.3 REFERENCES

- A. American National Standards Institute (ANSI): ANSI MH29.1 Safety Requirements for Industrial Scissor Lifts.

1.4 SUBMITTALS

- A. Submit under provisions of Section 01300.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Installation methods.
- C. Shop Drawings: Showing overall dimensions (width, height) and location of electrical service panels and motor locations. Supporting construction requirements and equipment structural attachment. Operating range and required clearances.
- D. Verification Samples: For each finish product specified, two samples, minimum size 6 inches (150 mm) square, representing actual product, color, and patterns.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Providing sole source for design, engineering, manufacturing and warranty claims handling. Company specializing in manufacturing products specified with a minimum 20 years experience.
- B. Installer Qualifications: Trained, certified and approved by manufacturer, with documented experience on similar projects.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened packaging until ready for installation.

1.7 PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's recommended limits.

1.8 WARRANTY

- A. Warranty: Provide manufacturer's standard warranty.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: Pentalift Equipment Corp., which is located at: 21 Nicholas Beaver Rd. ; Guelph, ON, Canada N1H 6H9 ; Tel: 519-763-3625; Fax: 519-763-2894; Email: [request info \(dock@pentalift.com\)](mailto:dock@pentalift.com); Web: www.pentalift.com
- B. Substitutions: Not permitted.
- C. Requests for substitutions will be considered in accordance with provisions of Section 01600.

Retractable Inflatable Dock Shelter:

1. Product: PSI-550 Retractable Inflatable Dock Shelter as manufactured by Pentalift Equipment Corporation.
2. Door opening _____ inches wide by _____ inches high.
3. Unit size shall be _____ inches wide by _____ inches high by _____ inches projection.
4. Bottom of wrap around side bags and header shall have breathers to allow for air and moisture discharge. Side bags, on pressure treated wood shall have internal retraction system and built in inflatable bottom pads.
5. Inflatable header assembly shall be installed in a full aluminum trimmed raked protective canopy, on pressure treated wood with the motor/ blower mounted to the underside.
6. Provide additional drop in head bag.
7. Unit when inflated shall allow unobstructed access to truck/trailer.
8. Cover fabric shall be _____.
9. Motor/blower shall be 1/2 hp, 115/1/60.
10. Motor/blower shall be 1/2 hp, 230/1/60.
11. Provide interlock to other dock equipment as indicated or required.
12. Unit to be supplied with manual on/off activation switch with overload protection and indicator light.

PART 3 EXECUTION

3.1 EXAMINATION.

- A. Do not begin installation until substrates have been properly prepared.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the

best result for the substrate under the project conditions.

3.3 INSTALLATION

A. Install in accordance with manufacturer's instructions.

3.4 PROTECTION

A. Protect installed products until completion of project.

B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION